

St Finian's School

This was a big project; the bottom of the tank had burst due to poor concrete grade eroding over the years.

What we did

- We cut out the bottom of the tank, where you can see a fix had been attempted with a metal plate.
- Removed the tank bottom, and failed pipework.
- New concrete with steel mesh.
- New pedestals and pipework, made to measure with our cutting and threading tool.
- Complete to existing discharge.
- Reused floats, panel and pumps.



About Flygt

The client is now on a 6-month service contract to ensure minimum disruption and downtime.

www.pumptechnologyservices.co.uk